

कुमाऊँ विश्वविद्यालय, नैनीताल

निविदा सूचना

अधोलिखित निर्माण/अनुरक्षण कार्य करने के लिए विश्वविद्यालय में पंजीकृत ठेकेदारों से दिनांक 11.11.2021 समय 1:00 बजे अपराह्न तक निविदा डाक/दस्ती/कोरियर के माध्यम से आमंत्रित की जाती हैं, जो उसी दिन अपराह्न 2:00 बजे खोली जाएंगी। निविदादाता उनके प्रतिनिधि निविदा खोलते समय उपस्थित रह सकते हैं। निविदा खुलने की तिथि में अवकाश होने पर निविदा अगले कार्य दिवस में खोली जाएंगी। निविदा फार्म को विश्वविद्यालय की वेबसाइट www.kunainital.ac.in से डाउनलोड किया जा सकता है। विस्तृत जानकारी हेतु विश्वविद्यालय के तकनीकी अनुभाग से सम्पर्क किया जा सकता है।

क्र० सं०	कार्य का नाम	अनुमानित लागत	धरोहर राशि	निविदा फार्म मूल्य	कार्य पूर्ण करने का समय
1	श्री कुवर सिंह बिष्ट, डरहम हाउस के आवास में निर्माण सम्बन्धी कार्य।	रु० 2,99,600	रु० 6000	रु० 590	30 दिन

कुलसचिव

कुमाऊँ विश्वविद्यालय, नैनीताल

दिनांक- 28/10/2021

पत्रांक-केयू/तकनीकी/2021/वि०नियो०/369

प्रतिलिपि- सूचनार्थ एवं वृहद प्रचारार्थ चस्पा करने हेतु-

- 1- श्री के०के० पाण्डे, कम्प्यूटर प्रोग्रामर, कुमाऊँ विश्वविद्यालय, नैनीताल को इस आशय से प्रेषित कि उक्त सूचना को विश्वविद्यालय वेबसाइट पर अपलोड करने हेतु।
- 2- विश्वविद्यालय में पंजीकृत ठेकेदारों को ई-मेल से सूचनार्थ प्रेषित।
- 3- सूचना पट्ट, प्रशासनिक भवन, कुमाऊँ विश्वविद्यालय, नैनीताल।

कुलसचिव

कुमाऊँ विश्वविद्यालय, नैनीताल

कुमाऊँ विश्वविद्यालय, नैनीताल



निविदा प्रपत्र

- 1-प्रत्येक कार्य हेतु पृथक-पृथक निविदा फार्म सीलबन्द लिफाफे में अधोहस्ताक्षरी के कार्यालय में निर्धारित तिथि एवं समय तक डॉक/निविदा बॉक्स में डाली जानी आवश्यक होगी।
- 2- प्रत्येक निविदा के साथ रू0 100 का नॉन ज्यूडिशियल स्टाम्प पर एक रुपये का हस्ताक्षरयुक्त रसीदी टिकट प्रेषित करना अनिवार्य होगा।
- 3-प्रत्येक निविदा के साथ निर्धारित धरोहर राशि एफ0डी0आर0/एन0एस0सी0 के रूप में वित्त अधिकारी, कुमाऊँ विश्वविद्यालय, नैनीताल के पक्ष में बन्धक बनाकर संलग्न करनी आवश्यक होगी।
- 4-निविदा फार्म निर्धारित शुल्क में लेखा अनुभाग से या वित्त अधिकारी के पदनाम से डिमांड ड्राफ्ट बनाकर प्राप्त किये जा सकते हैं।
- 5- निविदादाता को चाहिए कि वे निविदा देने से पूर्व कार्यस्थल का निरीक्षण कर लें।
- 6-समस्त कार्य लोक निर्माण विभाग द्वारा समय-समय पर निर्गत निर्धारित मानकों/शर्तों के अनुरूप सम्पादित किये जायेंगे।
- 7-किसी एक/समस्त निविदा को स्वीकृत/अस्वीकृत करने का अधिकार अधोहस्ताक्षरी के पास सुरक्षित होगा।

कुलसचिव

(10/5)

Kumaon University, Nainital

Tender Form

Name of work- Construction of Room & repair of old building allotted to Sri Kuwar sing at D.S.B. campus Nainital.

Date of colling tender-28-10-2021

Date of opening tender- 11-11-2021

Cost of tender form- Rs. 590.00

Earnest money- Rs. 6000.00

time of completion- 30 days

validity of tender- 45 days

S. N.	Particulars Item	Quantity	Unit	Estimeted Rate Rs.
1	Earth work in excavation in fundation mixed soil etc complete.	6.82	M ³	217.60
2	C.C. 1:4:8 with cement sand and 40 mm grit complete all.	1.84	M ³	6947.50
3	Brick work with 1:6 c/s mortar in foundation & plinth complete.	5.02	M ³	7388.90
4	Brick work with 1:6 c/s mortar in super structure complete.	6.88	M ³	9108.50
5	12 mm thick plaster with 1:6 c/s mortar complete.	79.50	M ²	305.10
6	oil bound distemper two coat with one coat rimer complete.	79.50	M ²	184.10
7	S/F of C.G.I. roofing complete with nut bolts washer 0.63 mm thick complete.	18.80	M ²	1098.00
8	S/F of hollow section pipe for builtup tube truss etc complete.	200.00	Kg	172.10
9	P/F G.I. metel ceilling with colour 595x595&0.5 mm thick complete all.	10.90	M ²	1805.30
10	P/F of flush door shutter 30 mm thick complete.	3.60	M ²	2183.75
11	S/F of iron chaukhat/frame etc work complete.	92.00	Kg	157.20
12	light point with 1.5 mm copper wire with earth wire and 20 mm pvc conduit complete.	6	point	694.00
13	S/F of submain with 2x2.5 mm +1x2.5 mm coper wire with 20 mm thick pvc conduit complete.	15.00	mt	167.00
14	R.C.C. 1:1.5:3 with cement sand and 20 mm stone ballast for slab/shelvs complete.	0.58	M ³	11167.20
15	M.S. plain iron work wrought to required shape bending cracking etc.	68.29	Kg	98.50
16	S/F of ceremic glazed floor tiles over 20 mm base 1:4 c.s. mortar complete.	11.90	M ²	1112.25
17	P/F of green marble stone for kitchen shelvs etc over base concrete etc.	1.80	M ²	2500.00
18	S/F of steel sink 2'x1.5' complete.	1	No	3000.00


Chauhan

19	S/F of 15 mm G.I. pipe complete fitting.	10.00	mt	341.85
20	Form work shuttering etc for slab/ shelves etc.	7.20	M ²	831.65

Note- All the work shall be carried out as per P.W.D specification & directed by Engineer I/C.

I/We tender.....% below/above on the given estimated rates.

Sing. of contractor
Address


Register
Kumaon University, Nainital
